Community	Placed	Reported extent (source)	Model GIS	Length (km)	Volume (10^6 yd^3)	Volume (10^6 m^3)	Density (m^3 m^{-1})	In model
Rodanthe 2014	2014-07-29 to 2014-09-20	2.13 mi from 1.5 mi north of the Pea Island refuge border south into Mirlo Beach (USACE public notice 2013, via Beachapedia)	82–88	3.5	1.62	1.24	354	yes
Buxton 2017	2017-06-21 to 2018-02-27	Haulover Day Use Area south to the groin at the old lighthouse site, 2.94 mi (Outer Banks Voice, 2018-03-01)	6–16	5.5	2.60	1.99	361	yes
Buxton 2022	2022-06-30 to 2022-08-16	Haulover Day Use Area to the lighthouse groin field, 2.9 mi (Dare County bulletin, 2022)	6–16	5.5	1.20	0.92	167	yes
Avon 2022	2022-06-19 to 2022-07-26	Due East Rd (3,000 ft north of Avon Pier) to the NPS/Avon boundary, 2.5 mi (Dare County)	21–28	4.0	1.00	0.76	191	yes
Buxton 2026	2026-07-31 to pending	Haulover area to the southernmost Buxton groin, about 2.9 mi (Island Free Press FAQ, 2026)	6–16	5.5	2.00	1.53	278	no
Avon 2026	2026-05-28 to 2026-06-25	Just south of Avon Pier to Greenwood Place, about 1 mi (Island Free Press, 2026)	22–26	2.5	0.38	0.29	115	no

Density: model volume spread evenly over the footprint's 500 m domains. 2026 fills fall after the CoastSat record (to 2026-01-13) and are not modelled; Buxton 2026 volume is planned, not as-built.